An Affine Semigroup from Orbifold Boundary Conditions: cut, phylogenetic and hierarchical models in the unit-weight sector, and weighted configurations beyond them (Part IX-B)

Combinatorial commutative algebra · affine semigroups and toric ideals

Carles Marín

Statements

Definition 1 3
Proposition 1 5
Theorem 1 — [8 , Cor. 3.4] 6
Proposition 2 7
Proposition 3 9
Proposition 4 10
Proposition 5 10

At a glance

What the paper contributes

The equivalence classes of orbifold boundary conditions are the elements of an **affine semigroup**: one generator per label of the alphabet of Part IX-A, graded by weight, embedded by its local data at the fixed points. The note identifies that semigroup and decides which of its cases are complete intersections.

- **The dictionary** (unit-weight sector), as an equality of point configurations: the cut configurations of P_3, C_4 and the wheel W_4 (Sturmfels–Sullivant); group-based models on claw trees; a mixed-order variant not located in the literature; binary hierarchical models of cross-polytope boundaries.
- **Thirteen complete intersections** with explicit gluing trees (unitary, orthogonal and symplectic alphabets); seven are weighted, outside every framework of the dictionary.
- **The tripod, decided** (Proposition 1): the group-based model on the tripod is a complete intersection exactly when $|G| \leq 3$, for every finite abelian group.
- **Every $k \geq 3$** (Proposition 2): $(S^1/\mathbb{Z}_2)^k$ is not a complete intersection, by the extreme-ray bound of Fischer–Morris–Shapiro (Theorem 1, cited), and not a cut ideal, by a count of edges.
- **The exceptional case** $S^1/\mathbb{Z}_2 \times S^1/\mathbb{Z}_2$: not a complete intersection by an exhaustive sweep (Proposition 3); a unique minimal Markov basis of 8 + 8 indispensable binomials in two orbits under an automorphism group of order 128 (Proposition 4); Cohen–Macaulay type 9 (Proposition 5).
- **Inherited**, and said so in the Ledger: the gluing criterion and the extreme-ray bound, the cut-ring invariants of W_4 (normality, degree 64, codimension 7), the group-based codimensions.

🚀 **Start here: Proposition 1**: the group-based tripod is a complete intersection exactly when $|G| \leq 3$.

Main results:


- **Proposition 1**: the group-based tripod is a complete intersection exactly when $|G| \leq 3$
- **Proposition 2**: $(S^1/Z_2)^k$ is not a complete intersection for any $k \geq 3$
- **Proposition 4**: unique minimal Markov basis: 8 quadrics + 8 quartics, all indispensable, two orbits under a group of order 128
- **Proposition 5**: Cohen–Macaulay type 9: canonical module generated in degrees 4 (one) and 6 (eight)

7 results | ✅ **0** entirely in Lean | ◐ **1** partly in Lean

💻 **5** checked by a program | written proof only (a result can carry several tags)

🗺️ Map of the results (click a box to go to it)

Dependencies in the written proof: an arrow A → B means that this proof of B uses A. Every result rests on its written proof; the tags record what was checked besides, and each statement's "Evidence & scope" block says how far. The colour of a box is its strongest tag, in the order above; the tags in the box give the rest. Boxes with a thick border are the main results; click a box to read the statement.



📐 Setting (copied from the paper, §1)

Let $L = \{\ell_1, \dots, \ell_n\}$ be the alphabet, $w_i \in \mathbb{Z}_{>0}$ the weight of ℓ_i and $v_i \in \mathbb{N}^c$ its local data. Put $a_i = (w_i, v_i) \in \mathbb{N}^{1+c}$ and let $S = \langle a_1, \dots, a_n \rangle \subseteq \mathbb{N}^{1+c}$ be the affine semigroup they generate. The number of equivalence classes of rank N is the number of elements of S in degree N, so the class-counting generating function is the Hilbert series $H(S, x)$. The lattice of relations $\mathcal{L} = \ker(\mathbb{Z}^n \to \mathbb{Z}^{1+c})$ has rank $n - \dim S$, and its elements are the moves preserving every local datum. *(§2)* On $(S^1/\mathbb{Z}_2)^k$ the ground set is the $2k$ reflections, in k antipodal pairs, and a fixed point is a choice of one reflection per circle. So the marginals are indexed by the 2^k *transversals*, which are the facets of the boundary complex of the k-dimensional cross-polytope: $n = 2^{2k} = 4^k$, $\dim S = \#\{\text{faces}\} = \sum_j \binom{k}{j} 2^j = 3^k$. *(§4)* For a partition $T = T_1 \sqcup T_2$ of the minimal generating set into non-empty parts, S is the *gluing* of $S_1 = \langle T_1 \rangle$ and $S_2 = \langle T_2 \rangle$ by α if $\alpha \in S_1 \cap S_2$, $\alpha \neq 0$, and $G(S_1) \cap G(S_2) = \mathbb{Z}\alpha$. Fischer, Morris and Shapiro prove that an affine semigroup which is not free is a complete intersection if and only if it is a gluing of two complete intersections. *(§5)* The smallest member of the group-based family is the claw tree with three leaves. The labels are the triples of group elements summing to zero, so $n = |G|^2$, and the local datum is the indicator of each entry.

What this blueprint shows.

The numbered statements of the paper, with their proofs, dependencies and what checked them, under the sections that hold them (with the paper's numbers), and the figures and tables they use. The full text is in the PDF of the paper.

1 The semigroup

Definition 1. p. 2

Let $L = \{\ell_1, \dots, \ell_n\}$ be the alphabet, $w_i \in \mathbb{Z}_{>0}$ the weight of ℓ_i and $v_i \in \mathbb{N}^c$ its local data. Put $a_i = (w_i, v_i) \in \mathbb{N}^{1+c}$ and let $S = \langle a_1, \dots, a_n \rangle \subseteq \mathbb{N}^{1+c}$ be the affine

semigroup they generate. The number of equivalence classes of rank N is the number of elements of S in degree N, so the class-counting generating function is the Hilbert series $H(S, x)$.

Lean · Mathlib, not ours **show**

The semigroup S is the submonoid generated by the vectors a_i, and an affine semigroup is a finitely generated, torsion-free commutative monoid: both notions are in Mathlib.

AddSubmonoid.closure · `Mathlib/Algebra/Group/Submonoid/Basic.lean`, line 112 (made by `@[to_additive]` from `Submonoid.closure`)

```
def closure (s : Set M) : Submonoid M
```

The `Submonoid` generated by a set.

IsAffineAddMonoid · `Mathlib/Algebra/AffineMonoid/Basic.lean`, line 20

```
class abbrev IsAffineAddMonoid (M : Type*) [AddCommMonoid M] : Prop
```

An affine monoid is a finitely generated cancellative torsion-free commutative monoid.

Mathlib commit `f0b4c8150aa0`, as this blueprint was built.

↳ Not used by another result of the paper.

orbifold	group	n	$\dim S$	rank $\mathcal{L}$	$H(S,x)$
$S^1/\mathbb{Z}_2$	$SU(N)$	4	3	1	$(1-x^2)/(1-x)^4$
$T^2/\mathbb{Z}_2$	$SU(N)$	8	5	3	$(1-x^2)^3/(1-x)^8$
$T^2/\mathbb{Z}_3$	$SU(N)$	9	7	2	$(1-x^3)^2/(1-x)^9$
$T^2/\mathbb{Z}_4$	$SU(N)$	10	8	2	$(1-x^4)^2/\left[(1-x)^8(1-x^2)^2\right]$
$T^2/\mathbb{Z}_6$	$SU(N)$	11	9	2	$(1-x^6)^2/\left[(1-x)^6(1-x^2)^3(1-x^3)^2\right]$
$T^2/\mathbb{Z}_4$	$SU(N)$, weight 1	8	7	1	$(1-x^4)/(1-x)^8$
$T^2/\mathbb{Z}_6$	$SU(N)$, weight 1	6	6	0	$1/(1-x)^6$
$T^2/\mathbb{Z}_3$	$SO(N)$	5	4	1	$(1-x^6)/\left[(1-x)(1-x^2)^4\right]$
$T^2/\mathbb{Z}_4$	$SO(N)$	8	6	2	$(1-x^4)^2/\left[(1-x)^4(1-x^2)^4\right]$
$T^2/\mathbb{Z}_6$	$SO(N)$	8	6	2	$(1-x^6)^2/\left[(1-x)^2(1-x^2)^3(1-x^3)^2(1$

$S^1/\mathbb{Z}_2 \times S^1/\mathbb{Z}_2$	$SU(N)$	16	9	7	$\dfrac{1+7x+20x^2+28x^3+7x^4+x^5}{(1-x)^9}$

Table 1: The family. The class counts of the first ten rows are in print in the physics literature [12 , 13 , 14 , 15] ; the last row is the one the companion note [1] derives, and is the only row of the table that is not a quotient by a cyclic rotation. The rows with a weight-1 alphabet are the ones §2 identifies with objects already studied in commutative algebra; the rows whose alphabet carries weights 2, 3 and 4 are §6.

Colour: blue shade = the number's size within its column.

5 The tripod, decided

Proposition 1. p. 6

> *Let G be a finite abelian group and let S be the semigroup of the group-based model on the tripod. Then S is a complete intersection if and only if $|G| \leq 3$: it is free for $|G| = 2$, a complete intersection with two cubics for $|G| = 3$, and not a complete intersection for $\mathbb{Z}_4$, for $\mathbb{Z}_2 \times \mathbb{Z}_2$, or for any abelian group of order at least 5.*

NEW **Classical and new:** the paper looked for this classification in the group-based literature and did not find it; what that literature settles for the tripod is normality, and the local (Zariski-open) complete intersection of [CFM] (§4, §6, Ledger).

↳ Not used by another result of the paper.

Proof

The labels are the triples of group elements summing to zero, so $n = |G|^2$, and the local datum is the indicator of each entry, so $\dim S = 3(|G|-1)+1 = 3|G|-2$ and the codimension is $(|G|-1)(|G|-2)$, which is the value the phylogenetics literature prints for the tripod.

Every generator is an extreme ray, by the argument of Proposition 2: it is a $0/1$ vector with one 1 in each of three blocks, hence one of the vertices of a product of three simplices, and a vertex stays extreme in the hull of any subset containing it. Nothing in that argument uses the group law beyond the fact that the labels select a subset of those vertices, so it holds unchanged for every finite abelian G and not only for the cyclic ones — which is what lets the bound below be quantified over all of them. Theorem 1 therefore requires

$$\boxed{|G|^2 \;\leq\; 2\dim S - 2 \;=\; 6|G| - 6, \qquad \text{that is} \qquad |G|^2 - 6|G| + 6 \leq 0,} \tag{1}$$

> which holds for $2 \le |G| \le 4$ and fails from 5 on: writing $f(g) = g^2 - 6g + 6$, one has $f(5) = 1 > 0$ and $f(g+1) - f(g) = 2g - 5 > 0$ for $g \ge 3$, so f is positive and increasing on the integers $g \ge 5$. The bound therefore settles every group of order five or more; the trivial group is outside its reach for the other reason, $\dim S = 1$ being below the $d \ge 2$ of Theorem 1, and its semigroup is $\mathbb{N}$, free. That leaves four groups open, of three orders: $\mathbb{Z}_2$, $\mathbb{Z}_3$, $\mathbb{Z}_4$ and $\mathbb{Z}_2 \times \mathbb{Z}_2$. Each of the four is decided by the gluing criterion, exhaustively — the two of order 4 over all $2^{15} - 1$ partitions of their sixteen generators — with the results of Table 3.

Evidence & scope

- **Program:** Z_2, Z_3, Z_4, $Z_2 \times Z_2$ by the gluing criterion (the order-4 groups over all $2^{15}-1$ partitions), with the codimension control $(|G|-1)(|G|-2)$. `scripts/tripod_gate.py`, `outputs/tripod_gate.txt`
- **By hand:** every order ≥ 5 by the extreme-ray bound $|G|^2 \le 6|G|-6$ of Theorem 1. `proof of Proposition 1`

G	$n = \lvert G\rvert^2$	$\dim S$	**codim**	$2 \dim S - 2$	**verdict**
$\mathbb{Z}_2$	4	4	0	6	free
$\mathbb{Z}_3$	9	7	2	12	complete intersection, degrees $[3, 3]$
$\mathbb{Z}_4$	16	10	6	18	not a complete intersection (swept)
$\mathbb{Z}_2 \times \mathbb{Z}_2$	16	10	6	18	not a complete intersection (swept)
$\lvert G\rvert \ge 5$	$\lvert G\rvert^2$	$3\lvert G\rvert - 2$	—	$6\lvert G\rvert - 6$	not a complete intersection ((4))

Table 3: The tripod, for every finite abelian group. The codimension is computed from the generator matrix and agrees with $(|G| - 1)(|G| - 2)$, which is a control that could have failed. The bound is silent exactly on the four small groups, which is why they are swept; and $\mathbb{Z}_2 \times \mathbb{Z}_2$ is the group of the Kimura 3-parameter model.

Colour: green = yes / holds; red = no / fails; grey = nothing; blue shade = the number's size within its column.

8 Every $k \ge 3$, in one line

Theorem 1. **([8 , Cor. 3.4])** p. 9

> *Let S be a d-dimensional affine semigroup which is a complete intersection, with $d \ge 2$. Then the cone of S has at most $2d - 2$ extreme rays.*

Lean · none found **show**

Searched on 20-oct-2026 (our Lean, Mathlib, Loogle, LeanSearch, GitHub; Isabelle not reached): not found. In this blueprint it enters Proposition 2 only as a hypothesis of the Lean statement, never as a proved fact.

🆕 **Classical and new:** cited, not claimed: Fischer, Morris and Shapiro [FMS, Cor. 3.4].

↳ Used in: Proposition 1 (p. 5), Proposition 2 (p. 7)

Proposition 2. 📕 p. 9

> *For every $k \geq 3$, the semigroup of $(S^1/\mathbb{Z}_2)^k$ is not a complete intersection.*

Lean · ours, in part **show**

added to the Lean repository after publication (20-oct-2026): the counts (4^k distinct generators, $\sum C(k,j)2^j = 3^k$), the arithmetic $4^k > 2\cdot 3^k - 2$ for $k \geq 3$ and equation (5); the proposition itself with Theorem 1 (Fischer–Morris–Shapiro, not in Mathlib) as a hypothesis; that every generator spans an extreme ray; and that the generators span a space of dimension 3^k for every k (the generator matrix is the k-th Kronecker power of a 4 × 4 matrix of rank 3, through a general rank(A ⊗ B) = rank A · rank B that we proved, since no library had it, in LinearAlgebra/Matrix/Rank/Kronecker.lean). Not in Lean: Theorem 1 itself (Fischer–Morris–Shapiro), which enters only as a hypothesis

- `OrbifoldProduct.not_completeIntersection_of_fms`
- `OrbifoldProduct.fms_bound_violated`
- `OrbifoldProduct.fms_bound_met`
- `OrbifoldProduct.card_labels`
- `OrbifoldProduct.marginal_injective`
- `OrbifoldProduct.sum_choose_mul_two_pow`
- `OrbifoldProduct.edges_exceed`
- `OrbifoldProduct.cut_vertices`
- `OrbifoldProduct.generator_extreme`
- `OrbifoldProduct.not_cone_of_others`
- `OrbifoldProduct.rank_generators`
- `OrbifoldProduct.generators_eq`
- `OrbifoldProduct.rank_circle`

Lean · Mathlib, not ours **show**

The count $\sum C(k,j)\cdot 2^j = 3^k$ (the dimension) is the binomial theorem of Mathlib; our proof uses it, it does not restate it.

add_pow · `Mathlib/Data/Nat/Choose/Sum.lean`, line 76

```
theorem add_pow [CommSemiring R] (x y : R) (n : ℕ) :
    (x + y) ^ n = ∑ m ∈ range (n + 1), x ^ m * y ^ (n - m) * n.choose m
```

The **binomial theorem**

Mathlib commit `f0b4c8150aa0`, as this blueprint was built.

✅ Checked when this page was built: OrbifoldProduct.lean compiles with Lean 4.35.0, no errors, no sorry. Axioms — not_completeIntersection_of_fms, fms_bound_violated, card_labels, sum_choose_mul_two_pow, edges_exceed, cut_vertices, generator_extreme, not_cone_of_others, rank_generators, generators_eq, rank_circle: propext, Classical.choice, Quot.sound; fms_bound_met:

propext; marginal_injective: propext, Quot.sound.

Reproduce: Lean 4.35.0, Mathlib f0b4c8150aa0; in that Lean project, `lake env lean OrbifoldProduct.lean` (SHA-256 of the compiled file: `c5e02635c60ff814…`; a source page on this site may show it with comments edited, under its own hash).

Trust base: 🔒 kernel only — **only part of the statement is formal** (see the box). Lean: 13 results, standard axioms only

Proof: in this note · **Covers:** not formalized · **Cite:** Proposition 1, p. 6, doi:10.5281/zenodo.22254864

🆕 **Classical and new:** claimed as the paper's own (Ledger), together with the edge count showing it is not a cut ideal for k ≥ 3; the bound it uses is Fischer–Morris–Shapiro [FMS, Cor. 3.4] (Theorem 1 of the paper, cited).

↳ Used in: Proposition 1 (p. 5)


Proof

Every generator is an extreme ray. A generator is a $0/1$ vector with exactly one 1 in each of the 2^k fixed-point blocks, so the generators are *a subset of* the vertex set of the product of the fixed-point simplices — a proper subset, since the product orbifold correlates the data at different fixed points and only 4^k of those vertices occur. That is enough: a vertex of a polytope remains extreme in the convex hull of any subset of the vertices containing it, and all the generators lie in one weight hyperplane, so each of them spans an extreme ray of the cone. With $n = 4^k$ and $d = 3^k$ from (2), Theorem 1 requires $4^k \le 2 \cdot 3^k - 2$, and $(4/3)^3 > 2$.

Evidence & scope

- **Program:** n = 4^k, d = 3^k, every generator extreme (integer Farkas certificates), k = 1..5; control: FMS Example 3.5 rebuilt for r = 1..4 attains 2d − 2 exactly, and two decoys. `scripts/fms_cone_gate.py`, `outputs/fms_cone_gate.txt`

Figure 2



Proposition 2, drawn: the extreme rays against the bound, and their ratio. The ratio is exactly 1 at $k = 1, 2$ — the bound is met, not approached — and exceeds 1 from $k = 3$. The ties are why $k = 2$ needed the exhaustive sweep, and why no inequality of this shape can separate a complete intersection from something meeting its bound exactly.

9 The exception, exhaustively

Proposition 3. p. 10

> *The semigroup of $S^1/\mathbb{Z}_2 \times S^1/\mathbb{Z}_2$ is not a complete intersection.*

Proof: in this note · **Covers:** not formalized · **Cite:** Proposition 3, p. 10, doi:10.5281/zenodo.22254864

NEW **Classical and new:** a direct argument independent of [SScuts, Table 1], which already records the cut ring of W_4 ($8 + 8$ minimal generators, codimension 7, degree 64) (§3, §8).

↳ Not used by another result of the paper.

Proof

It is not free: its relation lattice has rank 7. By [8] it is then a complete intersection if and only if some partition of its minimal generating set into two non-empty parts is a gluing. There are $2^{15} - 1 = 32767$ such partitions; testing each exactly, 16 survive the rank condition on the lattice intersection and none of those has an admissible α.

Evidence & scope

- **Program:** all 32767 partitions of the 16 labels: 16 survive the rank condition, none has an admissible gluing element. `scripts/gluing_tree.py`,

`outputs/gluing_tree.txt`

- **Program:** minimal Markov basis 8 + 8 against a relation lattice of rank 7. `scripts/complete_intersection.py`, `outputs/complete_intersection.txt`
- **Literature:** the same invariants in Sturmfels–Sullivant, Table 1 (row of the suspension of C_4). `[SScuts]`

Proposition 4. p. 11

> *On $S^1/\mathbb{Z}_2 \times S^1/\mathbb{Z}_2$ at rank 4, exactly eight fibres of the local-datum map are not connected by the degree-2 relations. Each of those fibres contains exactly two boundary conditions, and they are the only fibres of rank 4 with more than one component. The corresponding eight quartic binomials are therefore indispensable: each occurs, up to sign, in every Markov basis of the ideal. So are the eight quadrics, for the same reason at rank 2; hence*
>
> $$\text{the toric ideal has a \textit{unique} minimal binomial generating set, up to si}$$
> $$8 \text{ quadrics } + \text{ } 8 \text{ quartics.}$$
>
> *Under $\mathcal{G}$ the sixteen fall into exactly two orbits, one per degree.*

Proof: in this note · **Covers:** not formalized · **Cite:** Proposition 4, p. 11, doi:10.5281/zenodo.22254864

> NEW **Classical and new:** claimed as the paper's own (Ledger): uniqueness up to signs and the two orbits under Aut(A); the 8 + 8 count itself is in [SScuts, Table 1].

↳ Not used by another result of the paper.

Evidence & scope

- **Program:** the eight split fibres at rank 4 and the eight degree-4 generators are the same eight. `scripts/quartic_orbit_gate.py`, `outputs/quartic_orbit_gate.txt`
- **Program:** all sixteen indispensable; Aut(A) computed directly has order 128 and equals the group of seven involutions; orbits 8 + 8 (and the 8 canonical generators one orbit). `scripts/indispensable_gate.py`, `outputs/indispensable_gate.txt`

Proposition 5. p. 12

> *The semigroup ring of $S^1/\mathbb{Z}_2 \times S^1/\mathbb{Z}_2$ has Cohen–Macaulay type 9. Its canonical module has one minimal generator in degree $4 = \operatorname{codeg} P$ and eight in degree 6, and none in any other degree.*

Proof: in this note · **Covers:** not formalized · **Cite:** Proposition 5, p. 12, doi:10.5281/zenodo.22254864

> NEW **Classical and new:** claimed as the paper's own: the type 9 and the degrees of the canonical generators; normality, Cohen–Macaulayness and non-Gorensteinness are [SScuts, Table 1]


(Ledger).

↳ Not used by another result of the paper.

Evidence & scope

- **Program:** interior points 1, 16, 136, 752, 3097 in degrees 4–8 by enumeration and by $(-1)^d \mathrm{H}(1/x)$; minimal generators 1, 0, 8, 0, 0; Gorenstein decoy S^1/Z_2 returns type 1. `scripts/gorenstein_gate.py`, `outputs/gorenstein_gate.txt`
- **Program:** h*-vector (1,7,20,28,7,1) and the degree-2-moves series (1,7,20,28,15,−7). `scripts/formula_atlas.py`, `outputs/formula_atlas.txt`

Figure 3



The two counts of $S^1/\mathbb{Z}_2 \times S^1/\mathbb{Z}_2$ written over $(1-x)^9$. The first four coefficients agree; the last is negative on the right, and a lattice polytope cannot produce a negative h_i^*. The two series are $1, 16, 128, 688, \mathbf{2809}$ and $1, 16, 128, 688, \mathbf{2817}$.

invariant	value	source
vertices, dimension, facets	16, 8, 24	computed here
f-vector	$(1, 16, 104, 360, 712, 816, 520, 168, 24, 1)$	computed here
h^*-vector	$(1, 7, 20, 28, 7, 1)$	computed here
normalised volume	64	$\sum h_i^*$; also the degree in [2]
minimal generators	8 quadrics, 8 quartics	computed here; [2] , Table 1
normal, Cohen–Macaulay	yes, yes	[2] , Table 1
Gorenstein	no — Cohen–Macaulay **type** 9	computed here
codeg P, $a(k[S])$, reg $k[S]$	4, −4, 5	computed here

complete intersection	**no**	Proposition 3

Table 4: The exceptional case, as a list of invariants. It is a normal, Cohen–Macaulay toric ring which is not a complete intersection — which is the useful way to say what it is, rather than saying only what it is not.

Colour: green = yes / holds; red = no / fails.

📊 Tables

Every table of the paper, in its order: click one to unfold it, with where the paper cites it, how its numbers were checked, and its data as CSV. The typeset table is one click away, on its page of the PDF.

Table 1. The family. The class counts of the first ten rows are in print in the physics literature [HHK,KM,TI2,TI3]; the last row is the one the companion note [IXA] derives, and is the only row of the table that is not a quotient by a cyclic rotation. The rows with a weight-1 alphabet are the ones §2 identifies with objects already studied in commutative algebra; the rows whose alphabet carries weights 2, 3 and 4 are §6.

whiteorbifold	whitegroup	white n	white $\dim S$	whiterank $\mathcal{L}$	white $H(S,x)$
$S^1/\mathbb{Z}_2$	$SU(N)$	4	3	1	$(1-x^2)/(1-x)^4$
$T^2/\mathbb{Z}_2$	$SU(N)$	8	5	3	$(1-x^2)^3/(1-x)^8$
$T^2/\mathbb{Z}_3$	$SU(N)$	9	7	2	$(1-x^3)^2/(1-x)^9$
$T^2/\mathbb{Z}_4$	$SU(N)$	10	8	2	$(1-x^4)^2/\left[(1-x)^8(1-x^2)^2\right]$
$T^2/\mathbb{Z}_6$	$SU(N)$	11	9	2	$(1-x^6)^2/\left[(1-x)^6(1-x^2)^3(1-x^3)^2\right]$
$T^2/\mathbb{Z}_4$	$SU(N)$, weight 1	8	7	1	$(1-x^4)/(1-x)^8$
$T^2/\mathbb{Z}_6$	$SU(N)$, weight 1	6	6	0	$1/(1-x)^6$
$T^2/\mathbb{Z}_3$	$SO(N)$	5	4	1	$(1-x^6)/\left[(1-x)(1-x^2)^4\right]$
$T^2/\mathbb{Z}_4$	$SO(N)$	8	6	2	$(1-x^4)^2/\left[(1-x)^4(1-x^2)^4\right]$
$T^2/\mathbb{Z}_6$	$SO(N)$	8	6	2	$(1-x^6)^2/\left[(1-x)^2(1-x^2)^3(1-x^3)^2(1-\right.$
$S^1/\mathbb{Z}_2\times S^1/\mathbb{Z}_2$	$SU(N)$	16	9	7	$\dfrac{1+7x+20x^2+28x^3+7x^4+x^5}{(1-x)^9}$

Colour: blue shade = the number's size within its column.

p. 3 in the PDF | ⬇ CSV | cited in §1 The semigroup | cited in §2 What this semigroup already is | cited in §4 Thirteen gluings, read as exceptions

Table 2. Thirteen complete intersections. The two right-hand degree columns are computed by routes that do not communicate: the gluing degrees from lattice geometry, the numerator degrees from the Hilbert series. The last column says which framework the row belongs to; seven rows are weighted, and no framework in §2 covers those.

whiteorbifold	whitegroup	white n	whitegluing degrees	whitenumerator degrees	whitestatus
$S^1/\mathbb{Z}_2$	$SU(N)$	4	$[2]$	$[2]$	binary, [SScuts]
$T^2/\mathbb{Z}_2$	$SU(N)$	8	$[2,2,2]$	$[2,2,2]$	their Ex. 1.2
$T^2/\mathbb{Z}_3$	$SU(N)$	9	$[3,3]$	$[3,3]$	group-based, $\mathbb{Z}_3$ tripod
$T^2/\mathbb{Z}_4$	$SU(N)$, w. 1	8	$[4]$	$[4]$	group-based, mixed orders
$T^2/\mathbb{Z}_6$	$SU(N)$, w. 1	6	$[\,]$	$[\,]$	free, $\mathbb{N}^6$
$T^2/\mathbb{Z}_4$	$SU(N)$	10	$[4,4]$	$[4,4]$	**weighted**
$T^2/\mathbb{Z}_6$	$SU(N)$	11	$[6,6]$	$[6,6]$	**weighted**
$T^2/\mathbb{Z}_3$	$SO(N)$	5	$[6]$	$[6]$	**weighted**
$T^2/\mathbb{Z}_4$	$SO(N)$	8	$[4,4]$	$[4,4]$	**weighted**
$T^2/\mathbb{Z}_6$	$SO(N)$	8	$[6,6]$	$[6,6]$	**weighted**
$T^2/\mathbb{Z}_3$	$Sp(N)$	5	$[3]$	$[3]$	quaternionic
$T^2/\mathbb{Z}_4$	$Sp(N)$	8	$[4,4]$	$[4,4]$	**weighted**
$T^2/\mathbb{Z}_6$	$Sp(N)$	8	$[6,6]$	$[6,6]$	**weighted**

Colour: green = yes / holds; blue shade = the number's size within its column.

p. 5 in the PDF | ⬇ CSV | cited in §1 The semigroup | cited in §4 Thirteen gluings, read as exceptions | cited in §6 Where the weights take it outside | cited in §10 The marginal polytopes | cited in §A Reproducibility

Table without a number, in the text of §4 Thirteen gluings, read as exceptions

whiteorbifold	whiteover $SU(N)$	whiteover $SO(N)$	whiteover $Sp(N)$

$T^2/\mathbb{Z}_3$	$9{\times}1$, $[3,3]$	$1{\times}1 + 4{\times}2$, $[6]$	$5{\times}1$, $[3]$
$T^2/\mathbb{Z}_4$	$8{\times}1 + 2{\times}2$, $[4,4]$	$4{\times}1 + 4{\times}2$, $[4,4]$	$6{\times}1 + 2{\times}2$, $[4,4]$
$T^2/\mathbb{Z}_6$	$6{\times}1 + 3{\times}2 + 2{\times}3$, $[6,6]$	$2{\times}1 + 3{\times}2 + 2{\times}3 + 1{\times}4$, $[6,6]$	$4{\times}1 + 2{\times}2 + 2{\times}3$, $[6,6]$

⬇ CSV

Table 3. The tripod, for every finite abelian group. The codimension is computed from the generator matrix and agrees with $(|G|-1)(|G|-2)$, which is a control that could have failed. The bound is silent exactly on the four small groups, which is why they are swept; and $\mathbb{Z}_2 \times \mathbb{Z}_2$ is the group of the Kimura 3-parameter model.

white$G$	white $n = \lvert G\rvert^2$	white $\dim S$	whitecodim	white $2\dim S - 2$	whiteverdict
$\mathbb{Z}_2$	4	4	0	6	free
$\mathbb{Z}_3$	9	7	2	12	complete intersection, degrees $[3,3]$
$\mathbb{Z}_4$	16	10	6	18	not a complete intersection (swept)
$\mathbb{Z}_2 \times \mathbb{Z}_2$	16	10	6	18	not a complete intersection (swept)
$\lvert G\rvert \geq 5$	$\lvert G\rvert^2$	$3\lvert G\rvert - 2$	—	$6\lvert G\rvert - 6$	not a complete intersection \ (4)

Colour: green = yes / holds; red = no / fails; grey = nothing; blue shade = the number's size within its column.

p. 7 in the PDF ⬇ CSV cited in §5 The tripod, decided cited in §7 Local and global

Table without a number, in the text of §6 Where the weights take it outside

whitecone orders	whitestabilisers	whitetype	whiteconfiguration	whitename
equal	all full	complex	flows on a claw tree	group-based model [SSphylo]
equal, all 2	all full	complex	cuts of a graph	cut configuration [SScuts]
mixed	all full	complex	flows with $g_i \in H_i$	1, not located
any	some proper	complex	*weighted* flows	not located
any	any	real, quaternionic	weighted, recombined	not located

Colour: red = no / fails.

⬇ CSV

Table 4. The exceptional case, as a list of invariants. It is a normal, Cohen–Macaulay toric ring which is not a complete intersection — which is the useful way to say what it is, rather than saying only what it is not.

whiteinvariant	whitevalue	whitesource
vertices, dimension, facets	16, 8, 24	computed here
f-vector	$(1, 16, 104, 360, 712, 816, 520, 168, 24, 1)$	computed here
h^*-vector	$(1, 7, 20, 28, 7, 1)$	computed here
normalised volume	64	$\sum h_i^*$; also the degree in [SScuts]
minimal generators	8 quadrics, 8 quartics	computed here; [SScuts], Table 1
normal, Cohen–Macaulay	yes, yes	[SScuts], Table 1
Gorenstein	no — Cohen–Macaulay **type** 9	computed here
codeg P, $a(k[S])$, reg $k[S]$	4, -4, 5	computed here
complete intersection	**no**	Proposition 3

Colour: green = yes / holds; red = no / fails.

p. 12 in the PDF ⬇ CSV cited in the opening, before §1

Table 5. The marginal polytopes. Above the line the type is a free sum of simplices; below it is a cut polytope of a graph with a K_4 minor.

whiteorbifold	whitevertices	whitedim	whitecombinatorial type
$S^1/\mathbb{Z}_2$	4	2	$\Delta_1 \oplus \Delta_1$
$T^2/\mathbb{Z}_2$	8	4	$\Delta_1^{\oplus 4}$; also $\mathrm{Cut}^{\square}(C_4)$, as it must be
$T^2/\mathbb{Z}_3$	9	6	$\Delta_2 \oplus \Delta_2 \oplus \Delta_2$
$T^2/\mathbb{Z}_4$ (weight 1)	8	6	$\Delta_3 \oplus \Delta_3$
$T^2/\mathbb{Z}_6$ (weight 1)	6	5	Δ_5
$S^1/\mathbb{Z}_2 \times S^1/\mathbb{Z}_2$	16	8	$\mathrm{Cut}^{\square}(W_4)$

Colour: blue shade = the number's size within its column.

p. 13 in the PDF ⬇ CSV not cited in the text

Table 6. What each result owes.

whiteItem	whiteInherited (cite)	whiteOurs
complete intersection $\iff$ iterated gluing; the extreme-ray bound	Fischer–Morris–Shapiro [FMS]; Delorme [Delorme] in rank one	nothing
Hilbert series of a gluing 3	Assi–García-Sánchez–Ojeda [AGO]	nothing
cut ideals; the invariants of the cut ring of W_4 — codimension, degree, minimal generators; quadrics $\iff$ no K_4 minor	Sturmfels–Sullivant [SScuts]; Engström [Engstrom]	nothing
normality and Cohen–Macaulayness of the exceptional case, on which the reading of the numerator as an h^*-vector rests	Sturmfels–Sullivant [SScuts], Table 1	nothing
group-based models, their codimension, and that most are not complete intersections	Sturmfels–Sullivant [SSphylo]; Casanellas–Fern\'andez-S\'anchez–Michaek [CFM]	nothing
non-negativity of h^*	Stanley [Stanley]	nothing
that orbifold boundary conditions form these semigroups, and which graph, tree or complex each one is	—	**ours**
that each weighted alphabet is the minimal generating set	—	**ours**
the gluing trees of the weighted rows, and of the orthogonal and symplectic alphabets	—	**ours**
that the tripod is a complete intersection exactly for $\lvert G\rvert \le 3$, for every finite abelian G	—	**ours**
that $(S^1/\mathbb{Z}_2)^k$ is not a complete intersection for any $k \ge 3$, and is not a cut ideal	—	**ours**
the Cohen–Macaulay type, a-invariant and codegree of the exceptional case, and that its minimal Markov basis is unique up to signs, sixteen indispensable binomials in two orbits of eight under $\mathrm{Aut}(A)$	that it is normal and Cohen–Macaulay and not Gorenstein: [SScuts], Table 1	**ours** (the type 9 itself, and the degrees its canonical module is generated in)

Colour: green = yes / holds; blue = the paper's own; grey = nothing.

p. 13 in the PDF ⬇ CSV not cited in the text

Table without a number, in the text of §A Reproducibility

whitescript	whitewhat it establishes
`bc_preflight.py`	the alphabets, weights and local data, from the rotation matrix

`cut_ideal_gate.py`	that the labels are the cuts of P_3, C_4 and W_4, both directions
`gluing_tree.py`	the ten unitary and orthogonal gluing trees; the exhaustive sweep of the 32767 partitions
`tripod_gate.py`	the tripod for every finite abelian group, with the codimension control
`sp_gluing_gate.py`	the three symplectic gluing trees: minimality, gluings, degrees
`ledger_gate.py`	that every script this table names is on disk with its receipt, read out of this note's own source; and that $10 + 3 = 13$, with every row of Table 2 backed by exactly one of the two receipts and every receipt row used by exactly one table row
`gorenstein_gate.py`	the Cohen–Macaulay type, the a-invariant and codeg of the exceptional case, with a Gorenstein decoy
`quartic_orbit_gate.py`	the eight split fibres, the eight degree-4 generators, and that they are the same eight
`indispensable_gate.py`	Proposition 4: that all sixteen are indispensable, that $\mathrm{Aut}(A)$ has order 128, and the two binomial orbits together with the one of the canonical generators
`complete_intersection.py`	minimal Markov basis against lattice rank
`fms_cone_gate.py`	extreme rays, $n = 4^k$, $d = 3^k$, and the control on Example 3.5
`formula_atlas.py`	the Hilbert series and the two h^*-vectors
`polytope_id.py`	the combinatorial types of the marginal polytopes
`minimality_gate.py`	that every listed alphabet is the minimal generating set, with a decoy

⬇ CSV

References

1

C. Marín, *The Alphabet of Orbifold Boundary Conditions*, Part IX-A of this series, Zenodo, doi:10.5281/zenodo.22254861.

2

B. Sturmfels, S. Sullivant, *Toric geometry of cuts and splits*, Michigan Math. J. **57** (2008) 689–709, arXiv:math/0606683.

3

A. Engström, *Cut ideals of K_4-minor free graphs are generated by quadrics*, Michigan Math. J. **60** (2011) 705–714, arXiv:0805.1762.

4 B. Sturmfels, S. Sullivant, *Toric ideals of phylogenetic invariants*, J. Comput. Biol. **12** (2005) 204–228, arXiv:q-bio/0402015.

5 M. Casanellas, J. Fernández-Sánchez, M. Michałek, *Local description of phylogenetic group-based models*, arXiv:1402.6945.

6 M. Michałek, E. Ventura, *Finite phylogenetic complexity of $\mathbb{Z}_p$ and invariants for $\mathbb{Z}_3$*, J. Algebra (2017), arXiv:1508.04177.

7 M. Michałek, E. Ventura, *Phylogenetic complexity of the Kimura 3-parameter model*, arXiv:1704.02584.

8 K. G. Fischer, W. Morris, J. Shapiro, *Affine semigroup rings that are complete intersections*, Proc. Amer. Math. Soc. **125** (1997) 3137–3145. 🔎 find it

9 C. Delorme, *Sous-monoïdes d'intersection complète de N*, Ann. Sci. Éc. Norm. Supér. **9** (1976) 145–154. 🔎 find it

10 A. Assi, P. A. García-Sánchez, I. Ojeda, *Frobenius vectors, Hilbert series and gluings of affine semigroups*, J. Commut. Algebra **7** (2015) 317–335. 🔎 find it

11 R. P. Stanley, *Decompositions of rational convex polytopes*, Ann. Discrete Math. **6** (1980) 333–342. 🔎 find it

12 N. Haba, Y. Hosotani, Y. Kawamura, Prog. Theor. Phys. **111** (2004) 265. 🔎 find it

13 Y. Kawamura, T. Miura, Prog. Theor. Phys. **122** (2009) 847, arXiv:0905.4123.

14 K. Takeuchi, T. Inagaki, *Classification of $T^2/\mathbb{Z}_m$ orbifold boundary conditions*, arXiv:2404.19411.

15 K. Takeuchi, T. Inagaki, PTEP **2025** 043B03, arXiv:2501.05849.